

AD A099064

SUSQUEHANNA RIVER BASIN
KINGS CREEK, SULLIVAN COUNTY

PENNSYLVANIA


ROSCOE BURGESS DAM

NDI ID NO. PA-357

DER ID NO. 57-37

ROSCOE BURGESS

PHASE I INSPECTION REPORT



S MAY 18 1981

A

Prepared By
L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EBENSBURG, PENNSYLVANIA
15931

This document has been approved
for public release and sale; its
distribution is unlimited.

FOR
DEPARTMENT OF THE ARMY
BALTIMORE DISTRICT CORPS OF ENGINEERS
BALTIMORE, MARYLAND

21203

APRIL 1981

Original contains color
plates. All DTIC reproductions
will be in black and
white.

DTIC FILE COPY

81 5 18 013


SUSQUEHANNA RIVER BASIN
KINGS CREEK, SULLIVAN COUNTY

(1) PENNSYLVANIA
National Dam Inspection Report.
ROSCOE BURGESS DAM

Number
(NDI ID ~~NO~~ PA-357
Number
DER ID ~~NO~~ A 57-37)

Susquehanna River, Basin, Kings
ROSCOE BURGESS
Creek, Sullivan County, Pennsylvania.

PHASE I INSPECTION REPORT,



(12) 82

(15) DACW31-81-C-0012

Prepared By

L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EBENSBURG, PENNSYLVANIA

15931

FOR

DEPARTMENT OF THE ARMY
BALTIMORE DISTRICT CORPS OF ENGINEERS
BALTIMORE, MARYLAND
21203

(11) APR 10 1981

411059

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The spillway design flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

PHASE I REPORT
NATIONAL DAM INSPECTION REPORT

NAME OF DAM	Roscoe Burgess Dam
STATE LOCATED	Pennsylvania
COUNTY LOCATED	Sullivan
STREAM	Kings Creek
DATES OF INSPECTION	October 22, 1980
COORDINATES	Lat: 41° 34.2' Long: 76° 37.1'

ASSESSMENT

The assessment of the Roscoe Burgess Dam is based upon visual observations made at the time of inspection, review of available records and data, hydraulic and hydrologic computations and past operational performance.

The Roscoe Burgess Dam appears to be in fair condition. Maintenance of the dam is fair. The brush and small trees on the downstream slope and toe area of the structure should be removed. No drainline exists at the dam, which is considered a deficiency.

The Roscoe Burgess Dam is a high hazard-small size dam. The recommended spillway design flood (SDF) for a dam of this size and classification is in the range of 1/2 PMF to PMF. Based on the downstream potential for loss of life and property damage, the spillway design flood has been selected as the PMF. The spillway and reservoir are capable of controlling approximately 25% of the PMF without overtopping the embankment low spot. Based on criteria established by the Corps of Engineers, the spillway is termed inadequate, but not seriously inadequate.

The following recommendations and remedial measures should be instituted immediately.

1. A detailed hydrologic and hydraulic analysis should be conducted by a registered professional engineer knowledgeable in dam design and construction to increase the spillway capacity.


2. The brush and small trees on the downstream slope of embankment and in the area of the toe should be removed under the direction of a registered professional engineer knowledgeable in dam design and construction to insure that the removal of the vegetation does not seriously affect the stability of the structure.

ROSCOE BURGESS DAM
PA 357

3. No reservoir drain exists for the structure. This is considered a deficiency and some means, with an upstream control, should be provided to drain the reservoir should the need arise to do so.
4. A warning system should be developed to warn downstream residents of imminent failure of the dam.
5. A regularly scheduled maintenance program should be planned and implemented at the dam.
6. A safety inspection program should be implemented with inspections at regular intervals by qualified personnel.

SUBMITTED BY:

L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS AND ARCHITECTS



4-6-81

Date

R. Jeffrey Kimball

R. Jeffrey Kimball, P.E.


APPROVED BY:

21 APR 81

Date

James W. Peck

JAMES W. PECK
Colonel, Corps of Engineers
District Engineer



Overview of Roscoe Burgess Dam.

TABLE OF CONTENTS

	PAGE
SECTION 1 - PROJECT INFORMATION	1
1.1 General	1
1.2 Description of Project	1
1.3 Pertinent Data	3
SECTION 2 - ENGINEERING DATA	5
2.1 Design	5
2.2 Construction	5
2.3 Operation	5
2.4 Evaluation	5
SECTION 3 - VISUAL INSPECTION	6
3.1 Findings	6
3.2 Evaluation	7
SECTION 4 - OPERATIONAL PROCEDURES	8
4.1 Procedures	8
4.2 Maintenance of Dam	8
4.3 Maintenance of Operating Facilities	8
4.4 Warning System in Effect	8
4.5 Evaluation	8
SECTION 5 - HYDRAULICS AND HYDROLOGY	9
5.1 Evaluation of Features	9
5.2 Evaluation Assumptions	9
5.3 Summary of Overtopping analysis	10
5.4 Summary of Dam Breach Analysis	10
SECTION 6 - STRUCTURAL STABILITY	11
6.1 Evaluation of Structural Stability	11
SECTION 7 - ASSESSMENT AND RECOMMENDATIONS/REMEDIAL MEASURES	12
7.1 Dam Assessment	12
7.2 Recommendations/Remedial Measures	12

APPENDICES

- APPENDIX A - CHECKLIST, VISUAL INSPECTION, PHASE I
- APPENDIX B - CHECKLIST, ENGINEERING DATA, DESIGN, CONSTRUCTION,
OPERATION, PHASE I
- APPENDIX C - PHOTOGRAPHS
- APPENDIX D - HYDROLOGY AND HYDRAULICS
- APPENDIX E - DRAWINGS
- APPENDIX F - GEOLOGY

PHASE I
NATIONAL DAM INSPECTION PROGRAM

ROSCOE BURGESS DAM
NDI. I.D. NO. PA 357
DER I.D. NO. 57-37

SECTION 1
PROJECT INFORMATION

1.1 General.

a. Authority. The National Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of inspection of dams throughout the United States.

b. Purpose. The purpose of the inspection is to determine if the dam constitutes a hazard to human life or property.

1.2 Description of Project.

a. Dam and Appurtenances. The Roscoe Burgess Dam is an earth-fill dam, 264 feet long and 17 feet high. The crest width of the dam is 12 feet. The upstream and downstream slopes of the dam are 2H:1V. The upstream slope of the dam is protected with riprap, and the downstream slope of the dam is grass covered and contains considerable brush and small trees. A gravel roadway exists across the crest of the dam.

The spillway for the dam is located at the left abutment. The spillway is a rectangular structure with a weir length equal to 31.5 feet. The control section for the spillway consists of a semi-sharp crested weir. A 13 foot long concrete apron with an endsill is beyond the control section. Large boulders are located beyond the end sill and serve to protect the spillway channel from erosion due to discharges from the spillway. A concrete wingwall exists along the right edge of the spillway, and a wooden bridge spans the spillway crest area. The wooden bridge is supported by four wooden columns located near the center of the span.

b. Location. The dam is located on Kings Creek, approximately 4 miles north of the Village of Estella, Elkland Township, Sullivan County, Pennsylvania. The Roscoe Burgess Dam can be located on the Overton, U.S.G.S. 7.5 minute quadrangle.

c. Size Classification. The Roscoe Burgess Dam is a small size dam (17 feet high, 318 acre-feet).

d. Hazard Classification. The Roscoe Burgess Dam is a high hazard dam. Downstream conditions indicate that loss of more than a few lives is probable should the structure fail. The Village of Estella is located approximately 4 miles downstream of the dam.

e. Ownership. The Roscoe Burgess Dam is owned by Mr. Roscoe Burgess. Correspondence should be addressed to:

Mr. Roscoe Burgess
R.D. #1
Forkville, Pennsylvania 18616
717/924-3555

f. Purpose of Dam. The dam is utilized for recreational purposes.

g. Design and Construction History. Based on information contained in the PennDER files, a member of the Fish Commission first located the structure on April 7, 1948. Subsequent correspondence between the Fish Commission and the Water and Power Resources Board indicated that no permit had been issued for the construction of the dam. In April, 1948, Mr. Burgess was contacted by appropriate state officials and was asked to submit plans and other pertinent information to the Board.

Later correspondence in the file indicates that the dam was completed in 1947. The length of the reservoir and embankment were estimated at 1,000 feet and 500 feet, respectively. It was reported at this time that no permit was requested since it was understood that the drainage area was significantly less than 1/2 square mile.

In January, 1949, an application was made by Mr. Burgess requesting that a permit be issued for his dam. The report on the application indicated that the dam was only partially constructed. The structure was to have a total length of 300 feet and a maximum height of 16 feet. During March, 1949, the Department of Forest and Waters received a letter regarding the Roscoe Burgess Dam. It was reported in the letter that the dam had failed and that a considerable amount of property damage had occurred due to the failure. No loss of life was associated with the failure. During April, 1949, the structure was inspected by an engineer from the Water and Resources Board. As a result of the inspection it was suggested that Mr. Burgess retain an engineer to prepare plans for the structure. No information relative to the reported failure was contained in the inspection memorandum. Construction of the present dam was completed late 1951. The engineer who designed the dam was Mr. Jesse S. Ritchey of Wellsboro, Pennsylvania. A construction survey was completed by Mr. Samuel R. Kirkland, a registered surveyor from Laporte, Pennsylvania. Drawings relative to the structure appear in Appendix E of this report. No information relative to the actual construction of the dam was available.

h. Normal Operating Procedures. No operations are conducted at the dam. Normal inflow to the reservoir is maintained at the spillway crest elevation.

1.3 Pertinent Data.

a. Drainage Area. 1.61 square miles

b. Discharge at Dam Site (cfs).

Maximum flood at dam site	Unknown
Spillway capacity at top of dam	1060 cfs

c. Elevation (U.S.G.S. Datum) (feet). - Field survey based on the spillway crest elevation, 1672.0 feet from drawings. See Appendix E, page E-5.

Top of dam - low point	1676.7
Top of dam - design height	1676.0
Pool at time of inspection	1671.5
Spillway crest	1672.0
Maximum pool - design surcharge	Unknown
Normal pool	1672.0
Maximum tailwater	Unknown
Toe of dam	1659.5

d. Reservoir (feet).

Length of maximum pool (PMF)	2700
Length of normal pool	1900

e. Storage (acre-feet).

Normal pool (spillway crest)	105
Top of dam	318

f. Reservoir Surface (acres).

Top of dam	65
Normal pool	28.5
Spillway crest	28.5

g. Dam.

Type	Earthfill
Length (including spillway)	264 feet
Height	17 feet
Top width	12 feet
Side slopes - upstream	2H:1V
- downstream	2H:1V
Zoning	None
Impervious core	None
Cutoff	None
Grout curtain	None

h. Reservoir Drain. (None)

i. Spillway.

Type	Semi-sharp crest
Length	31.5 feet
Crest elevation	1672.0
Upstream channel	Lake
	(unrestricted)
Downstream channel	Kings Creek

SECTION 2 ENGINEERING DATA

2.1 Design. Review of available information in the files of the Commonwealth of Pennsylvania, Department of Environmental Resources, revealed that some correspondence, permit information, design drawings, and pictures were available for review. Drawings relative to the design of the Roscoe Burgess Dam are located in Appendix E of this report.

2.2 Construction. No information exists regarding the construction of the dam.

2.3 Operation. No operations are conducted at the dam.

2.4 Evaluation.

a. Availability. Engineering data were provided by the PennDER, Bureau of Dams and Waterway Management. The owner of the dam, Mr. Roscoe Burgess, was interviewed to obtain data relative to the dam. Mr. Burgess did not supply any additional information.

b. Adequacy. This Phase I Report is based on the visual inspection and hydrologic and hydraulic analysis. Sufficient information exists to complete a Phase I Report.

SECTION 3
VISUAL INSPECTION

3.1 Findings.

a. General. The onsite inspection of the Roscoe Burgess Dam was conducted by personnel of L. Robert Kimball and Associates on October 22, 1980. The inspection consisted of:

- 1, Visual inspection of the retaining structure, abutments and toe.
- 2, Examination of the spillway facilities, exposed portion of any outlet works and other appurtenant works.
3. Observations affecting the runoff potential of the drainage basin.
4. Evaluation of the downstream area hazard potential.

b. Dam. The dam appears to be in fair condition. From a brief survey conducted during the inspection, it was noted that the low area on the crest of the dam was located at the right abutment. Riprap was observed on the upstream slope of the structure approximately 2 feet above the waterline at the time of inspection. A roadway was observed to exist across the entire length of the embankment. The downstream slope of the dam was covered with small trees and brush. The brush on the downstream slope hampered attempts at close visual inspection of the slope and toe area.

c. Appurtenant Structures. The spillway for the dam is located at the left abutment of the structure. A wooden bridge was observed which spans the spillway crest. A concrete sidewall is present along the right edge of the spillway. A cutoff wall exists perpendicular to the right spillway channel wall. The control section for the spillway is a semi-sharp crested structure. A concrete stilling basin exists below the control section with an endsill at the downstream end of the stilling basin. Large boulders were observed in the channel immediately below the spillway. The boulders are used to protect the channel immediately below the spillway from erosion. The spillway is a near rectangular section. Four wooden columns exist at the spillway approach and are utilized to support the wooden bridge which spans the spillway crest area. No spillway approach wingwalls were observed at the structure. The spillway appeared to be in fair condition and adequately maintained. No drainline was observed existing at the dam.

d. Reservoir Area. The watershed is covered almost entirely with forested lands. The reservoir slopes are moderate and do not appear to be susceptible to landslides which would affect the storage volume of the reservoir or overtopping of the dam by displacing water.

e. Downstream Channel. The downstream channel for the Roscoe Burgess Dam consists of Kings Creek. The Village of Estella is located approximately 4 miles downstream of the dam. The population of the village is approximately 50 people. Route 154 passes through the Village of Estella and crosses Kings Creek at the Village.

3.2 Evaluation. In general, the dam and appurtenant structures appear to be in fair condition. No major erosion areas were observed during the inspection. No seepage was observed along the downstream slope of the structure or along the toe area. Dense brush exists along the downstream slope of the structure and hampered attempts at close visual inspection of the downstream slope and toe area. The brush and small trees on the downstream slope and in the area of the toe of the dam should be removed under the direction of a registered professional engineer. Once the slope and toe area are cleared, the area should be reinspected to verify that no seepage existed at the structure.

No drainline was observed at the structure. This is considered a deficiency and some means should be provided to drain the reservoir.

SECTION 4
OPERATIONAL PROCEDURES

4.1 Procedures. The reservoir is maintained at the spillway crest elevation. No other procedures are conducted at the dam.

4.2 Maintenance of the Dam. No planned maintenance schedule exists for the dam. Maintenance of the dam is performed by the owner on an unscheduled, as-needed basis. Small trees and brush exist on the downstream slope and toe area of the structure. The small trees and brush should be cleared from the slope and toe area.

4.3 Maintenance of Operating Facilities. No operating facilities exist at the structure. Normal inflow to the reservoir is discharged through the spillway at the left abutment. No erosion was observed at the approach to the spillway.

4.4 Warning System in Effect. There is no warning system in effect to warn downstream residents of imminent failure of the dam.

4.5 Evaluation. Maintenance of the dam is considered fair. Brush and small trees have been allowed to grow on the downstream slope of the structure. The brush and small trees should be removed from the downstream slope and toe area to enable close inspection of the slope and toe area for possible seepage.

An emergency action plan should be available for every dam in the high and significant category. Such plans should outline actions to be taken by the operator to minimize downstream effects of an emergency and should include an effective warning system. No emergency action plan has been developed, and the owner should develop such a plan.

SECTION 5 HYDRAULICS AND HYDROLOGY

5.1 Evaluation of Features.

a. Design Data. Limited information relative to the hydraulic design of the spillway were available for review. Available information contained in the DER files indicates that a design discharge capacity of 1500 cfs was considered for the structure. The design capacity was associated with a spillway crest length of 35 feet and an available head of 5 feet. It is apparent that the design capacity is less than that recommended by current guidelines.

b. Experience Data. No rainfall, runoff or reservoir level data were available. The spillway reportedly has functioned adequately in the past.

c. Visual Observations. The spillway appeared to be in fair condition and adequately maintained. No erosion of the spillway approach was observed during the inspection, but the potential exists for erosion of the earthen embankment at the right of the spillway approach.

The low spot on the embankment crest was observed to exist at the right abutment of the structure.

d. Overtopping Potential. Overtopping potential was investigated through the development of the probable maximum flood (PMF) for the watershed and the subsequent routing of the PMF and fractions of the PMF through the reservoir and spillway.

The Corps of Engineers, Baltimore District, has directed that the HEC-1 Dam Safety Version systemized computer program be utilized. The program was prepared by the Hydrologic Engineering Center (HEC), U.S. Army Corps of Engineers, Davis, California, July, 1978. The major methodologies or key input data for this program are discussed briefly in Appendix D.

5.2 Evaluation Assumptions. To complete the hydraulic and hydrologic analysis for this structure, it was necessary to make the following assumptions.

1. Pool elevation in the reservoir prior to the storm was assumed to be at the spillway crest elevation, 1672.0.

2. The top of dam was considered to be the low spot elevation at the right abutment, 1676.7.

3. The control section at the spillway was considered as exhibiting the characteristics of a semi-sharp crested weir. The crest elevation was considered to be a constant elevation along its entire length. The spillway was considered to be rectangular section for the purposes of this analysis.

5.3 Summary of Overtopping Analysis. Complete summary sheets for the computer output are presented in Appendix D.

Peak inflow (PMF)	5800 cfs
Spillway capacity	1060 cfs

a. Spillway Adequacy Rating. The Spillway Design Flood (SDF) is based on the hazard and size classification of the dam. The recommended spillway design flood for a dam of this size and classification is in the range of 1/2 PMF to PMF. Based on the potential for loss of life and property damage, the spillway design flood has been selected as the PMF. Based on the following definition provided by the Corps of Engineers, the spillway is rated as inadequate as a result of our hydrologic analysis.

Inadequate - All high hazard dams which do not pass the spillway design flood (PMF).

The spillway and reservoir are capable of controlling approximately 25% of the PMF without overtopping the embankment.

5.4 Summary of Dam Breach Analysis. The analysis indicates the subject dam cannot satisfactorily pass 50% of the PMF, it was necessary to perform the dam breach analysis and downstream routing of the flood wave. This analysis determined the degree of increased flooding and due to dam failure. A pool elevation of 1678.0 was considered as sufficient to cause failure of the dam due to overtopping.

Results of the dam breach analysis indicate that the downstream potential for loss of life and property damage is not significantly increased by dam failure from that which existed just prior to the failure. Therefore, the spillway is rated as inadequate, but not seriously inadequate. Details of the downstream routing of the flood wave are included in Appendix D.

SECTION 6 STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability.

a. Visual Observations. No visible deficiencies were observed on the embankment which would affect the stability of the structure. No erosion was observed on the embankment crest or slopes. No seepage was observed during the inspection. The downstream slope and toe area of the structure were covered with small trees and brush which hampered attempts at close visual inspection of the slope and toe area. The small trees and brush should be removed from the slope and toe area, and the area reinspected to verify that no seepage exists at the structure.

The spillway appeared to be in fair condition and adequately maintained. No visible deficiencies were observed at the structure which would affect the discharge capability of the structure. It was observed during the inspection that no protection exists along the embankment at the approach to the spillway. During periods of large discharges at the spillway the potential exists for erosion of the right edge of the spillway approach. This erosion could cause damage to the embankment in the area of the spillway.

b. Design and Construction Data. No information was available in the DER files relative to the construction of the dam. The existing dam appears to have been the result of design modifications to an original structure which existed in 1948. The design modifications culminated in the subsequent completion of the original structure. The modifications to the design of the present structure were completed by Mr. Jesse S. Richey, an engineer from Wellsboro, Pennsylvania. The construction of the dam was apparently completed under the direction of the owner, and the construction was completed sometime in late 1951.

c. Operating Records. No operating records exist for the dam.

d. Post Construction Changes. No post construction changes are known to have occurred since construction of the dam was completed in 1951.

e. Seismic Stability. The dam is located in seismic zone 1. No seismic stability analyses has been performed. Normally, it can be considered that if a dam in this zone is stable under static loading conditions, it can be assumed safe for any expected earthquake loading. Since no signs of instability were noted during the inspection, the Roscoe Burgess Dam is assumed to be safe for earthquake loading.

SECTION 7
ASSESSMENT AND RECOMMENDATIONS/REMEDIAL MEASURES

7.1 Dam Assessment.

a. Safety. The dam appears to be in fair condition and fairly well maintained. No erosion was observed on the embankment crest or slopes. No seepage was observed on the downstream slope of the dam or along the toe area.

The potential for erosion exists on the embankment in the area of the spillway approach. No spillway approach wingwall exists at the structure at this location. No erosion in the area was observed during the inspection but during periods of increased inflow to the reservoir the potential for large discharges at the spillway include the potential for erosion of the embankment at the approach to the spillway. No drainline exists for the reservoir which is considered a deficiency.

The visual observations, review of available data, hydrologic and hydraulic calculations and past operational performance indicate that the Roscoe Burgess Dam is capable of controlling approximately 25% of the PMF. If the low spot on the embankment crest adjacent to the right abutment were filled to an elevation consistent with the remaining portion of the crest, no significant increase in the storage and discharge potential of the spillway and reservoir would be realized. The spillway is termed inadequate.

b. Adequacy of Information. Sufficient information is available to complete a Phase I report.

c. Urgency. The recommendations suggested below should be implemented as soon as possible

d. Necessity for Further Investigation. In order to accomplish some of the recommendations/remedial measures outlined below, further investigations will be required by a professional engineer knowledgeable in dam design and construction.

7.2 Recommendations/Remedial Measures.

1. A detailed hydrologic and hydraulic analysis should be conducted by a registered professional engineer knowledgeable in dam design and construction to increase the spillway capacity.

2. The brush and small trees on the downstream slope of embankment and in the area of the toe should be removed under the direction of a registered professional engineer knowledgeable in dam design and construction to insure that the removal of the vegetation does not seriously affect the stability of the structure.

3. No reservoir drain exists for the structure. This is considered a deficiency and some means, with an upstream control, should be provided to drain the reservoir should the need arise to do so.

4. A warning system should be developed to warn downstream residents of imminent failure of the dam.

5. A regularly scheduled maintenance program should be planned and implemented at the dam.

6. A safety inspection program should be implemented with inspections at regular intervals by qualified personnel.

APPENDIX A
CHECKLIST, VISUAL INSPECTION, PHASE I

CHECK LIST
VISUAL INSPECTION
PHASE I

NAME OF DAM Roscoe Burgess Dam COUNTY Sullivan STATE Pennsylvania ID# 357
TYPE OF DAM Earthfill HAZARD CATEGORY High
DATE(s) INSPECTION October 22, 1980 WEATHER Clear and cold. TEMPERATURE 20°
POOL ELEVATION AT TIME OF INSPECTION 1671.5 M.S.L. TAILWATER AT TIME OF INSPECTION None M.S.L.

INSPECTION PERSONNEL:

R. Jeffrey Kimball, P.E. - L. Robert Kimball and Associates

James T. Hockensmith - L. Robert Kimball and Associates

O.T. McConnell - L. Robert Kimball and Associates

O.T. McConnell RECORDER

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS	None noted.	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None noted.	
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	None noted.	
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Appears to be all right.	
RIPRAP FAILURES	None.	

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
VEGETATION	Brush and small trees exist on the downstream slope of the dam and along the area of the toe.	The brush and trees should be removed from the embankment slope and toe area.
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	The low spot on the embankment crest was observed to exist at the right abutment of the dam. It was observed that the potential for erosion of the embankment exists at the spillway approach.	
ANY NOTICEABLE SEEPAGE	No seepage observed. The downstream slope and toe area of the structure were covered with vegetation which hampered attempts at close visual inspection of the slope and toe.	Brush and small trees should be removed and the slope and toe area reinspected to verify that no seepage exists.
STAFF GAUGE AND RECORDER	None.	
DRAINS	None.	

CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
ANY NOTICEABLE SEEPAGE	Not applicable.	
STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS	Not applicable.	
DRAINS	Not applicable.	
WATER PASSAGES	Not applicable.	
FOUNDATION	Not applicable.	

CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES	Not applicable.	
STRUCTURAL CRACKING	Not applicable.	
VERTICAL AND HORIZONTAL ALIGNMENT	Not applicable.	
MONOLITH JOINTS	Not applicable.	
CONSTRUCTION JOINTS	Not applicable.	
STAFF GAUGE OR RECORDER	Not applicable.	

OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	Not applicable.	
INTAKE STRUCTURE	Not applicable.	
OUTLET STRUCTURE	Not applicable.	
OUTLET CHANNEL	Not applicable.	
EMERGENCY GATE	Not applicable.	

UNGATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR	The spillway appeared to be in fair condition and fairly well maintained. No deficiencies were observed in the area of the spillway which would affect the discharge potential of the spillway.	
APPROACH CHANNEL	The potential for erosion of the embankment in the area of the approach exists.	
DISCHARGE CHANNEL	The discharge channel is clear of any debris and appears capable of discharging flows from the spillway.	
BRIDGE AND PIERS	A wooden bridge exists across the area of the spillway. Wooden piers support the bridge near mid-span.	

GATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE SILL	Not applicable.	
APPROACH CHANNEL	Not applicable.	
DISCHARGE CHANNEL	Not applicable.	
BRIDGE AND PIERS	Not applicable.	
GATES AND OPERATION EQUIPMENT	Not applicable.	

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	The spillway discharge channel for the Roscoe Burgess Dam consists of Kings Creek. No obstructions or debris were observed in the channel.	
SLOPES	Appear to be stable.	
APPROXIMATE NO. OF HOMES AND POPULATION	The Village of Estella is located approximately 4 miles downstream of the dam. The population of the village is estimated at approximately 50 people.	

RESERVOIR

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SLOPES	Moderate.	
SEDIMENTATION	Unknown.	

INSTRUMENTATION

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
MONUMENTATION/SURVEYS	None.	
OBSERVATION WELLS	None.	
WEIRS	None.	
PIEZOMETERS	None.	
OTHER	None.	



POOL
+1671.5

WOODEN
BRIDGE

LOW SPOT
1676.7

+1679.1 + 1677.5+ GRAVEL ROAD +1676.9 1677.5+ 1677.7+ 1676.9+ 1677.0 1682.6+

HEAVY BRUSH & TREES

1659.5

STILLING BASIN


1672.0
1667.4 +

RIPRAP




ROSCOE BURGESS DAM
SCALE: 1"=40'

A-12



SPILLWAY PROFILE
LOOKING UPSTREAM
NO SCALE



PROFILE
LOOKING UPSTREAM
SCALE : HORIZ. 1" = 40'
VERT. 1" = 20'



ROScoe BURGESS DAM

APPENDIX B
CHECKLIST, ENGINEERING DATA, DESIGN, CONSTRUCTION, OPERATION, PHASE I

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION
PHASE I

NAME OF DAM Roscoe Burgess Dam

ID# 357


ITEM	REMARKS
AS-BUILT DRAWINGS	None.
REGIONAL VICINITY MAP	U.S.G.S. quadrangle.
CONSTRUCTION HISTORY	Limited information available in DER files.
TYPICAL SECTIONS OF DAM	See Appendix E.
OUTLETS - PLAN - DETAILS - CONSTRAINTS - DISCHARGE RATINGS RAINFALL/RESERVOIR RECORDS	See Appendix E. See Appendix E. See Appendix E. None. None.

ITEM	REMARKS
DESIGN REPORTS	Unknown.
GEOLOGY REPORTS	Unknown.
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	None.
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	None.
POST-CONSTRUCTION SURVEYS OF DAM	None known to have occurred.
BORROW SOURCES	Unknown.

ITEM	REMARKS
MONITORING SYSTEMS	None.
MODIFICATIONS	None known to exist since construction of the structure.
HIGH POOL RECORDS	None.
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	None known to exist.
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	None known to have occurred since construction of the dam was completed in 1951.
MAINTENANCE OPERATION RECORDS	None.

ITEM	REMARKS
SPILLWAY PLAN SECTIONS DETAILS	See Appendix F.
OPERATING EQUIPMENT PLANS & DETAILS	None.

APPENDIX C
PHOTOGRAPHS



C - 1

ROScoe BURGESS DAM PHOTO INDEX

P - INDICATES PHOTO LOCATION



ROSCOE BURGESS DAM
PA 357

Sheet 1

Front



- (1) Upper left - View of the embankment crest and downstream slope. View towards the left abutment.
- (2) Upper right - View of the crest and upstream slope. View towards the right abutment.
- (3) Lower left - Spillway approach. Note the wooden bridge which spans the spillway crest.
- (4) Lower right - View of the spillway crest.


Back

- (5) Upper left - Discharge channel.
- (6) Upper right - Downstream exposure.

TOP OF PAGE

1,5	2,6
3	4





APPENDIX D
HYDROLOGY AND HYDRAULICS

APPENDIX D
HYDROLOGY AND HYDRAULICS

Methodology. The dam overtopping and breach analyses were accomplished using the systemized computer program HEC-1 (Dam Safety Investigation), September, 1978, prepared by the Hydrologic Engineering Center, U.S. Army Corps of Engineers, Davis, California. A brief description of the methodology used in the analysis is presented below.

1. Precipitation. The Probable Maximum Precipitation (PMP) is derived and determined from regional charts prepared from past rainfall records including "Hydrometeorological Report No. 33" prepared by the U.S. Weather Bureau.

The index rainfall may be reduced from 10% to 20% depending on watershed size by utilization of what is termed the HOP Brook adjustment factor. Distribution of the total rainfall is made by the computer program using distribution methods developed by the Corps.

2. Inflow Hydrograph. The hydrologic analysis used in development of the overtopping potential is based on applying a hypothetical storm to a unit hydrograph to obtain the inflow hydrograph for reservoir routing.

The unit hydrograph is developed using the Snyder method. This method requires calculation of several key parameters. The following list gives these parameters their definition and how they were obtained for these analysis.

Parameter	Definition	Where Obtained
Ct	Coefficient representing variations of watershed	From Corps of Engineers*
L	Length of main stream channel miles	From U.S.G.S. 7.5 minute topographic
Lca	Length on main stream to centroid of watershed	From U.S.G.S. 7.5 minute topographic
Cp	Peaking coefficient	From Corps of Engineers*
A	Watershed size	From U.S.G.S. 7.5 minute topographic

*Developed by the Corps of Engineers on a regional basis for Pennsylvania.

3. Routing. Reservoir routing is accomplished by using Modified Plus routing techniques where the flood hydrograph is routed through reservoir storage. Hydraulic capacities of the outlet works, spillways and the crest of the dam are used as outlet controls in the routing.

The hydraulic capacity of the outlet works can either be calculated and input or sufficient dimensions input, and the program will calculate an elevation discharge relationship.

Storage in the pool area is defined by an area - elevation relationship from which the computer calculates storage. Surface areas are either planimeted from available mapping or U.S.G.S. 7.5 minute series topographic maps or taken from reasonably accurate design data.

4. Dam Overtopping. Using given percentages of the PMF, the computer program will calculate the percentage of the PMF, which can be controlled by the reservoir and spillway without the dam overtopping.

5. Dam Breach and Downstream Routing. The computer program is equipped to determine the increase in downstream flooding due to failure of the dam caused by overtopping. This is accomplished by routing both the pre-failure peak flow and the peak flow through the breach (calculated by the computer with given input assumptions) at a given point in time and determining the water depth in the downstream channel. Channel cross-sections taken from U.S.G.S. 7.5 minute topographic maps were used in the downstream flood wave routing. Pre and post failure water depths are calculated at locations where cross-sections are input.

HYDROLOGY AND HYDRAULICS ANALYSIS DATA BASE

NAME OF DAM: Roscoe Burgess Dam

PROBABLE MAXIMUM PRECIPITATION (PMP) = 22.2 (0.98) = 21.76 inches

STATION	1	2	3
---------	---	---	---

Station Description

Drainage Area (square miles)	1.61
---------------------------------	------

Cumulative Drainage Area (square miles)	1.61
--	------

Adjustment of PMF for Drainage Area (%) ⁽¹⁾	
6 hours	117
12 hours	127
24 hours	136
48 hours	143
72 hours	145

Snyder Hydrograph Parameters	
Zone ⁽²⁾	17
Cp ⁽³⁾	0.45
Ct ⁽³⁾	1.13
L (miles) ⁽⁴⁾	1.45
Lca (miles) ⁽⁴⁾	0.57
tp = Ct(LxLca) 0.3 hrs.	1.08

Spillway Data	
Crest Length (ft)	31.5
Freeboard (ft)	4.7
Discharge Coefficient	3.3
Exponent	1.5

- (1) Hydrometeorological Report 40 (Figure 1), U.S. Weather Bureau and U.S. Army Corps of Engineers, 1965.
- (2) Hydrological zone defined by Corps of Engineers, Baltimore District, for determining Snyder's coefficients (C_p and C_t).
- (3) Snyder's Coefficients.
- (4) L=Length of longest water course from outlet to basin divide.
 L_{ca} =Length of water course from outlet to point opposite the centroid of drainage area.

CHECK LIST
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: 1.61 sq. mi.

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 1672.0 [105 ac-ft]

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): 1676.7 [318 ac-ft]

ELEVATION MAXIMUM DESIGN POOL: 1676.0

ELEVATION TOP DAM: 1676.7

SPILLWAY CREST:

- a. Elevation 1672.0
- b. Type Semi-sharp crest
- c. Width Crest length=31.5 feet
- d. Length Approximately 25 feet
- e. Location Spillover Left abutment
- f. Number and Type of Gates None

OUTLET WORKS:

- a. Type None
- b. Location None
- c. Entrance inverts None
- d. Exit inverts None
- e. Emergency drawdown facilities None

HYDROMETEOROLOGICAL GAUGES:

- a. Type None
- b. Location None
- c. Records None

MAXIMUM NON-DAMAGING DISCHARGE: Unknown

NSU

NAME ROBERT E. KIMBALL & ASSOCIATES

NUMBER 4-35

L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EDENSBURG PENNSYLVANIA

SHEET NO. OF

BY JKM DATE 3-9

BASE DATA FOR BASE FLOW PARAMETERS

AS RECOMMENDED BY THE DISTRICT OFFICE OF THE
CORPS OF ENGINEERS.

STRT = 1.00
STRT = 0.05
STRT = 1.00
STRT = 0.05 (FOR 1.00 FLOW)
STRT = 1.00

ELEVATION AREA-CAPACITY RELATIONSHIP

FOR 1.00 1.5 MIN. DURATION, 100 YEAR FLOOD
FLOOD PROTECTION DATA.

RELATIONSHIP ELEVATION = 1.00
AREA OF 1.00 AT ELEVATION 1.00 = 1.00
ELEVATION WHERE AREA EQUALS 1.00 = 1.00

FROM 1.00 1.5 MIN. DURATION 100 YEAR FLOOD
FLOOD HYDROGRAPH PACKAGE (HECH), FLOW RATE
VERSION (USERS MANUAL).

$$H = 3 Y / A$$

$$11 = 3 Y / 23.5$$

$$\therefore Y = 11(23.5) / 3$$

$$Y = 104.5 \text{ AC-FT}$$


AT ELEV. 1.00 AREA = 74 ACES
AT ELEV. 1.00 AREA = 1 ACES

TOP OF DAM LOW STAGE ELEVATION = 1.00

L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EBENSBURG PENNSYLVANIA

NAME _____
NUMBER PA-357

SHEET NO. 2 OF 4
BY JMA DATE 3/81



AREA	10	20	30	40	50
ELEVATION	1000.0	1001.2	1001.7	1002.0	1002.5


RAILWAY REST


$$L = \frac{1}{2} L^2 \quad \text{USE } C = 3.3 \text{ (SEMI-CIRCULAR REST)}$$

$$L = 31.5' \quad \text{AREA = 100 ACRES}$$

$$L = \frac{1}{2} L^2 \quad \text{USE } C = 3.0 \text{ (ROAD REST)}$$

$$L = 100 ACRES WITH 11'$$





L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EBENSBURG PENNSYLVANIA

NAME _____
NUMBER PA-357
SHEET NO. 3 OF 4
BY OTM DATE 3/81

EATING CURVE INCLUDES OVERTOPPING.

ELEV. (FT.)	SPILLWAY			OVERTOPPING			DISCHARGE *Q (CFS)
	H (FT.)	L (FT.)	Q (CFS)	H (FT.)	L (FT.)	Q (CFS)	
1672	0	31.5'	0				0
1672.5	0.5	"	35				35
1673	1	"	105				105
1673.5	1.5	"	190				190
1674	2	"	295				295
1675	3	"	540				540
1676.7	4.7	"	1060				1060
1678				1.3	293'	1,300	2,360
1680				3.3	334'	6,005	7,065
1682				5.3	372'	13,615	14,675

* Q ROUNDED TO NEAREST 5 CFS.

BREACH ANALYSIS

THE HEC-1 PMF ANALYSIS INDICATES THAT THE ROSCOE BURGESS DAM IS OVERTOPPED BY 1.33 FEET DURING THE V_2 PMF. THE OVERTOPPING IS CONSIDERED TO BE OF A MAGNITUDE AND DURATION SUFFICIENT TO CAUSE FAILURE OF THE DAM.

THE MAXIMUM OVERTOPPING (1.33') OCCURS AT THE RIGHT ABUTMENT. THE RIGHT ABUTMENT AREA APPEARED TO BE CAPABLE OF SUSTAINING LIMITED OVERTOPPING. THEREFORE, FOR THE PURPOSE OF ANALYSIS THE BEACH IS ASSUMED TO OCCUR NEAR M.O.-EMBANKMENT.




L. ROBERT KIMBALL & ASSOCIATES
CONSULTING ENGINEERS & ARCHITECTS
EBENSBURG PENNSYLVANIA

NAME _____
NUMBER PA - 357

SHEET NO. 4 OF 4
BY OTM DATE 3/81

FROM FIG ON PAGE 2 OF 4



BEWID = 30'
Z = 0.5
ELBM = 1661
-TAL = 2 HRS.
WSEL = 1672
FRIEL = 1678

0.5 PMF UTILIZED FOR
BREACH ANALYSIS.

BEACH CROSS-SECTIONS FROM I.S.G.S. CONC. SEE
PAGE D-15 AND E-1.

OVERBANK MANNINGS' $n = 0.06$ (ASSUMED)
CHANNEL MANNINGS' $n = 0.05$ (ASSUMED).

$\frac{2}{3}$

ANALYSIS OF DAM OVERTOPPING USING RATIOS OF THE PMF HYDROLOGIC-HYDRAULIC ANALYSIS OF SAFETY OF BURGESS RATIOS OF PMF ROUTED THROUGH THE RESERVOIR (PA-357)

1	A1	
2	A2	
3	A3	
4	B	288
5	B1	5
6	J	1
7	J1	0
8	K	0
9	K1	1
10	M	
11	P	
12	I	
13	W	1.08
14	X	-1.5
15	K	1
16	K1	1
17	Y	
18	Y1	1
19	Y4	1672
20	V5	0
21	SA	0
22	SE	1661
23	SS	1672
24	SD	1676.7
25	K	99

D-9

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 01 APR 80

RUN DATE= 81/03/05.
 TIME= 17.30.38.

ANALYSIS OF DAM OVERTOPPING USING RATIOS OF THE PMF
 HYDROLOGIC-HYDRAULIC ANALYSIS OF SAFETY OF BURGESS DAM
 RATIOS OF PMF ROUTED THROUGH THE RESERVOIR (PA-357)

JOB SPECIFICATION

NO	NHR	NMIN	IDAY	IHR	IMIN	METRC	IPLT	IPRT	NSTAN
288	15	0	0	0	0	0	0	0	0
	JUPER	5	0	0	0	TRACE			

MULTI-PLAN ANALYSES TO BE PERFORMED

RTIOS= .10 .50 1.00
 NPLAN= 1 NRTIO= 3 LRIO= 1

710

SUB-AREA RUNOFF COMPUTATION

INFLOW

ISTAQ	IComp	IECON	ITAPE	JPLT	IPRT	INAME	TESTAGE	TAUTO
1	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

IMYDG	IUNG	TAREA	SNAP	TNSDA	TKSPC	RATIO	ISNOW	ISAME	LOCAL
1	1	1.61	0.00	1.61	1.00	0.000	0	1	0

PRECIP DATA

SPFE	PMS	R6	R12	R24	R48	R72	R96
0.00	21.76	117.00	127.00	136.00	143.00	145.00	0.00

LOSS DATA

LRPT	STRKR	DLTKR	RTIOL	ERAIN	STKRS	RTIOK	STRTL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.05	0.00	0.00

UNIT HYDROGRAPH DATA

TP= 1.08 CP= .45 NIA= 0

REFLECTION DATA

STRIU= -1.50 URCSN= -.05 RTIOR= 2.00
APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 4.61 AND R= 6.92 INTERVALS

UNIT HYDROGRAPH 40 END-OF-PERIOD ORDINATES, IAG= 1.08 HOURS, CP= .45 VOL= 1.00									
40.	148.	286.	395.	424.	386.	334.	289.	250.	216.
187.	162.	140.	121.	105.	91.	78.	68.	59.	51.
44.	38.	33.	28.	25.	21.	18.	16.	14.	12.

4/6

HYDROGRAPH ROUTING

ROUTE THROUGH BURGESS

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPR1	INAME	ISTAGE	AUTO
2	1	0	0	0	0	1	0	0
ROUTING DATA								
OLOSS	CLOSS	AVG	IRRES	ISAME	LOPT	IPMP	LSTR	
0.0	0.000	0.00	1	1	0	0	0	

NSTPS	NSTD1	LAG	AMSK	X	TSK	STORA	ISPRAT
1	0	0	0.000	0.000	0.000	-1672.	-1
STAGE	1672.00	1673.00	1673.50	1674.00	1675.00	1676.70	1678.00
7/1682.00							1680.00
FLOW	0.00	35.00	105.00	295.00	540.00	1060.00	2360.00
7/1675.00							7065.00

SURFACE AREA= 0. 29. 65. 74. 119.

CAPACITY= 0. 105. 318. 548. 2460.

ELEVATION= 1661. 1672. 1677. 1680. 1700.

CREL	SPWID	COOW	EXPW	ELEV	COOL	CAREA	EXPL
1672.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

DAM DATA			
TOPEL	COOD	EXPD	DAMWID
1676.7	0.0	0.0	0.

D-13

HYDROGRAPH AT	1	1.61 (4.17)	1	579. (16.40)	2896. (82.02)	5793. (164.04)
ROUTED TO	2	1.61 (4.17)	1	383. (10.84)	2437. (69.02)	5458. (154.54)

D-13

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM	DURATION OVER TOP HOURS	MAXIMUM OUTFLOW CFS	MAXIMUM STORAGE AC-FT	MAXIMUM DEPTH OVER DAM	RATIO OF PMF	MAXIMUM RESERVOIR W.S.-ELEV	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
1672.00 105. 0.	1672.00 105. 0.	1672.00 105. 0.	1676.70 318. 1060.	0.00 4.25 7.25	383. 2437. 5458.	190. 407. 498.	0.00 1.33 2.62	.10 .50 1.00	1674.36 1678.03 1679.32	42.75 41.75 41.25	0.00 0.00 0.00

FLOOD HYDROGRAPH PACKAGE (HEC-1)
DAM SAFETY VERSION JULY 1978
LAST MODIFICATION 01 APR 80

1 A1 RATIOS OF PMF ROUTED THROUGH THE RESERVOIR AND DOWNSTREAM
2 A2 DOWNSTREAM CONDITIONS DUE TO OVERTOPPING OF HURGUSS DAM
3 A3 PLAN 1 ASSUMES BREACH, PLAN 2 ASSUMES NO BREACH (PA-357)
4 B 288 0 15 0 0 0 0 0
5 B1 5 1 1
6 J 2 1 1
7 J1 .5
8 K 0
9 K1 INFLOW 1
10 M 1 1.61 1
11 P 1 21.76 117 127 136 143 145 1.0 0.05
12 T
13 W 1.08 0.45
14 X -1.5 -.05 2.0
15 K 1
16 K1 ROUTE THROUGH BURGESS
17 Y
18 Y1
19 Y4 1672 1672.5 1673 1673.5 1674 1675 1676.7 1678 -1
20 Y5 0 35 105 190 295 540 1060 2360 1680 1682
21 SA 0 28.5 65 74 119 7065 14675
22 SE 1661 1672 1676.7 1680 1700
23 \$ 1672
24 \$D1676.7
25 \$B 30 0.5 1661 2 1672 1678
26 \$B 30 0.5 1661 2 1672 1680
27 K 1
28 K1 REACH NO. 1
29 Y
30 Y1 1
31 Y6 .06 .05 .06 1508 1540 11000 0.014 508 1508
32 Y7 0 1540 80 1520 500 1510 502 1508
33 Y7 510 1510 700 1520 820 1540
34 K 1
35 K1 REACH NO. 2
36 Y
37 Y1 1
38 Y6 .06 .05 .06 1348 1380 10000 0.016 133 1348
39 Y7 0 1380 50 1360 125 1350 127 1348
40 Y7 135 1350 200 1360 400 1380
41 K 99

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 01 APR 80

RUN DATE* 81/03/09.
 TIME* 12.18.03.

RATIOS OF PMF ROUTED THROUGH THE RESERVOIR AND DOWNSTREAM
 DOWNSTREAM CONDITIONS DUE TO OVERTOPPING OF BURGESS DAM
 PLAN 1 ASSUMES BREACH, PLAN 2 ASSUMES NO BREACH (PA-357)

JOB SPECIFICATION

NQ	NHR	NMIN	IDAY	IHR	IMIN	METRC	IPLT	IPRT	NSTAN
288	70	15	0	0	0	0	0	0	0
	JUPER		5	0	0	0			
				0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED

NPLAN= 2 NR10= 1 LRT10= 1

RTIOS= .50

SUB-AREA RUNOFF COMPUTATION

INFLOW

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	TAUTO
1	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

IMYDG	IUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	1	1.61	0.00	1.61	1.00	0.000	0	1	0

PRECIP DATA

SPFE	PMS	R6	R12	R24	R48	R72	R96
0.00	21.76	117.00	127.00	136.00	143.00	145.00	0.00

LOSS DATA

LROPT	STKR	DLTKR	RTIOL	ERAIN	STKRS	RTIOK	STRTL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.05	0.00	0.00

UNIT HYDROGRAPH DATA

TP= 1.08 CP= .45 NIA= 0

RECESSION DATA
 SIRTU= -1.50 URCSN= -.05 M10R= 2.00
 APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE IC= 4.61 AND R= 6.92 INTERVALS

UNIT	HYDROGRAPH	40	END-OF-PLRIOD	ORIGINATES,	LAG=	1.08	HOURS,	CP=	.45	VOL=	1.00
40.	148.	286.	395.	424.	380.	334.	334.	289.	250.	216.	
187.	162.	140.	121.	105.	91.	78.	78.	68.	59.	51.	
44.	38.	33.	28.	25.	21.	18.	18.	16.	14.	12.	

4/2

HYDROGRAPH ROUTING

REACH NO. 1

ISTAG	ICOMP	IFCOH	ITADE	JPLI	JPRI	INAME	ISTAGE	IAUTO
3	1	0	0	0	0	1	0	0
ALL PLANS HAVE SAME ROUTING DATA								
QLOSS	CLOSS	AVG	IRFS	ISAME	IPMP	LSTR		
0.0	0.000	0.00	1	1	0	0		
NSTPS	NSTDL	LAG	AMSKA	X	TSK	STORA	ISPRAT	
1	0	0	0.000	0.000	0.000	0.	0	

NORMAL DEPTH CHANNEL ROUTING

QNI(1)	QNI(2)	QNI(3)	ELNVT	FLMAX	RLNTH	SFL
0.0600	0.0500	0.0600	1508.0	1540.0	11000.	0.01400

CROSS SECTION COORDINATES--STA=ELEV,STA,LLV--LTC

0.00	1540.00	80.00	1520.00	500.00	1510.00	502.00	1508.00	508.00	1508.00
510.00	1510.00	700.00	1520.00	820.00	1540.00				
STORAGE									
0.00	3.27	21.92	83.52	188.82	337.81	530.49	766.88	1032.97	
1587.21	1875.07	2170.10	2472.29	2781.64	3098.16	3421.84	3752.68	4090.69	
OUTFLOW									
0.00	51.60	325.43	1519.40	4262.16	9061.16	16365.00	26584.31	42134.23	
82841.10	107439.61	134761.78	164755.64	197383.83	232619.88	270445.62	310849.41	353824.85	
STAGE									
1508.00	1509.68	1511.37	1513.05	1514.74	1516.42	1518.11	1519.79	1521.47	
1524.84	1526.53	1528.21	1529.89	1531.58	1533.26	1534.95	1536.63	1538.22	
FLOW									
0.00	51.60	325.43	1519.40	4262.16	9061.16	16365.00	26584.31	42134.23	
82841.10	107439.61	134761.78	164755.64	197383.83	232619.88	270445.62	310849.41	353824.85	

HYDROGRAPH ROUTING

REACH NO. 2

ISTAQ	ICOMP	ELCON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
4	1	0	0	0	0	1	0	0

ALL PLANS HAVE SAME
ROUTING DATA

QLOSS	CLOSS	AVG	IRLS	ISAME	IOPT	ISMP	LSTR
0.0	0.000	0.00	1	1	0	0	0

NSIPS	NSTD	LAG	AMSK	X	ISK	STOKA	ISPRAT
1	0	0	0.000	0.000	0.000	0	0

NORMAL DEPTH CHANNEL ROUTING

QN(1)	QN(2)	QN(3)	ELNVT	ELMAX	RINTH	SEL
0.000	0.0500	0.0600	1348.0	1380.0	10000.	0.01600

CROSS SECTION COORDINATES--STA.ELEV.STA.LEVEL--LIC
0.00 1380.00 50.00 1360.00 125.00 1350.00 127.00 1348.00 133.00 1348.00
135.00 1350.00 200.00 1360.00 400.00 1380.00

STORAGE	0.00	2.97	9.82	25.66	50.60	84.67	127.85	180.15	241.19
//1310.38									

	387.71	473.18	566.78	668.53	778.42	896.45	1022.61	1156.92	1299.37
//1449.95									

OUTFLOW	0.00	55.16	240.41	711.08	1609.19	3053.48	5149.89	7995.96	11758.03
316464.06									

	22157.63	28896.19	36738.90	45745.16	55973.99	67483.74	80331.95	94575.29	110269.58
127469.76									

STAGE	1348.00	1349.68	1351.37	1353.05	1354.74	1356.42	1358.11	1359.79	1361.47
//1363.16									

	1364.84	1366.53	1368.21	1369.89	1371.58	1373.26	1374.95	1376.63	1378.32
//1380.00									

FLOW	0.00	55.16	240.41	711.08	1609.19	3053.48	5149.89	7995.96	11758.03
116464.06									

	22157.63	28896.19	36738.90	45745.16	55973.99	67483.74	80331.95	94575.29	110269.58
127469.76									

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

RATIOS APPLIED TO FLOWS

OPERATION	STATION	AREA	PLAN	RATIO	1
					.50
HYDROGRAPH AT	1	1.61	1	2896.	
	(4.17)	(82.02)	(
ROUTED TO	2	1.61	2	2896.	
	(4.17)	(82.02)	(
ROUTED TO	3	1.61	1	5061.	
	(4.17)	(143.30)	(
ROUTED TO	4	1.61	2	2437.	
	(4.17)	(67.02)	(
ROUTED TO	5	1.61	1	4335.	
	(4.17)	(122.75)	(
ROUTED TO	6	1.61	2	2316.	
	(4.17)	(65.57)	(
ROUTED TO	7	1.61	1	4172.	
	(4.17)	(118.13)	(
ROUTED TO	8	1.61	2	2287.	
	(4.17)	(64.77)	(

Summary of Dam Safety Analysis


PLAN 1

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	INITIAL VALUE		MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TOP OF DAM		TIME OF FAILURE HOURS
			ELEVATION STORAGE OUTFLOW	1672.00 105. 0.				1672.00 105. 0.	1676.70 318. 1060.	
.50	1678.03	1.33			407.	5061.	7.63		43.50	41.50


PLAN 2

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	INITIAL VALUE		MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TOP OF DAM		TIME OF FAILURE HOURS
			ELEVATION STORAGE OUTFLOW	1672.00 105. 0.				1672.00 105. 0.	1676.70 318. 1060.	
.50	1678.03	1.33			407.	2437.	4.25		41.75	0.00


APPENDIX E
DRAWINGS




~~Com~~ MATCH TO BOTTOM OF E-1




LOCATION PLAN
REACH No. 2



Section of A wall
to be built on dam side of Spillway
Use full height for 10', then taper to end
Section up stream 7.5' and downstream 6'




Section in Spillway looking away from dam
All Concrete to be 1 part cement, 2 parts sand, 4 parts gravel



Area wooded watershed 1.25 sq. mi. Probable Maximum runoff 1150 Sec. ft.
 Flow in spillway "Kutters Formula" $n = .02$ $S = .02$ $R = 2.0$ water 24" deep = 1485 Sec. ft.
 Flow over submerged weir "Fteley and Sterns Formula" $H = 5.0'$ $H^2 = 1.6'$ $M = 320 = 1169$ Sec. ft.
 Area flooded = 20 ± Acres

Steel reinforcing should be expanded metal fabric weighing approx 65 lbs. a square of 100"



14-12-3



parts gravel or crushed stone.


Roscoe Burgess, owner

BURGESS DAM
 Kings Creek, Elkland Twp. Sullivan Co. Pa

Scale - 1/2" = 1'

Spillway details by J. B. Ritchey 1/4/50






BURGESS DAM
 Kings Creek, Elkland Twp Sullivan Co., Pa.
 Surveyed Sept. 2, 1949 by J. B. Ritchey
 Hor. Scale - 1" = 20' Vert Scale - 1" = 10'

Elev. Water in Pond
 74
 80

0+34


0+50



— Profile of Sections 9-2-49
 - - - Top Water Elev 904 9-2-49
 Material to be added
 91.0 Elev of Water when Complete


BU

in Pond 904




BURGESS DAM X-sections


Taken 7-2-1949 by *g. Reedy*
Scale - 1" = 10'




~ PLAN ~
Scale: 1" = 20' ft



SECTION A-A
Scale: 1" = 10 ft




SECTION B-B
Scale: 1" = 5 ft.





SECTION C-C
Scale: 1" = 5 ft

Slope Wall

1670



PLAN OF PROPOSED CONSTRUCTION
OF AN EARTH DAM AND A CONCRETE
SPILLWAY. TO BE CONSTRUCTED
FOR ROSCOE BURGESS.
SITUATED IN ELKLAND TOWNSHIP,
SULLIVAN COUNTY, PA.
SCALE AS SHOWN ON PLAN.
SAMUEL R. KIRKLAND
REGISTERED SURVEYOR
LAPORTE, PA. JULY 18, 1949.



SITE LOCATION MAP
SULLIVAN COUNTY, PENNSYLVANIA


APPENDIX F
GEOLOGY

General Geology

The Roscoe Burgess Dam is located in the (Glaciated) Low Plateaus Section of the Appalachian Plateau Province, near the boundary of the Allegheny High Plateaus Section. The surface is dissected, leaving remnants of what was once the high plateau. The region was covered by the Wisconsin glacier, which has left abundant evidence of its previous existence in the form of many small glacial lakes, marshes, and moraines. Deposits of glacial outwash are the most productive water-bearing materials in the area.

The bedrock underlying the dam consists of sandstones, shales, and graywackes of the Susquehanna Group of Upper Devonian Age. This group is divided into three formations, the Owayo Formation (youngest), the Catskill Formation, and the Marine Beds (oldest), which include the 'Chemung' and 'Portage' beds. The Roscoe Burgess Dam lies on the Catskill side of the Catskill/Chemung contact.

These strata strike to the northeast and dip to the northwest. This structural nature is due to the dam being located on a common limb of the Barclay Syncline to the northwest and Wilmot Anticline to the southeast. The geologic structure is typical of the Plateaus province, where the principal folds trend northeast. No major faulting is indicated in the vicinity of the Roscoe Burgess Dam.



GEOLOGIC MAP OF AREA AROUND SAXE POND DAM, ROSCOE BURGESS DAM AND THE BIRCH CREEK DAM

SCALE 1:250,000

PENNSYLVANIAN



Po Pottsville Formation
 A massive, gray, crystalline limestone, locally containing thin layers of shale and sandstone. It is the base of the Pennsylvanian in this area.

MISSISSIPPIAN



M March Creek Formation
 A massive, gray, crystalline limestone, locally containing thin layers of shale and sandstone. It is the base of the Mississippian in this area.



Mp Mokoma Group
 A massive, gray, crystalline limestone, locally containing thin layers of shale and sandstone. It is the base of the Mississippian in this area.

DEVONIAN

UPPER CENTRAL AND EASTERN PENNSYLVANIA



Ds Susquehanna Group
 A massive, gray, crystalline limestone, locally containing thin layers of shale and sandstone. It is the base of the Devonian in this area.



Ds Susquehanna Group
 A massive, gray, crystalline limestone, locally containing thin layers of shale and sandstone. It is the base of the Devonian in this area.



Ds Susquehanna Group
 A massive, gray, crystalline limestone, locally containing thin layers of shale and sandstone. It is the base of the Devonian in this area.



Ds Susquehanna Group
 A massive, gray, crystalline limestone, locally containing thin layers of shale and sandstone. It is the base of the Devonian in this area.

